DO NOT SCALE FROM THIS DRAWING

NOTES
1. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS NOTED OTHERWISE
2. ALL LEVELS ARE IN METRES AOD UNLESS NOTED OTHERWISE.
3. TO BE READ IN CONJUNCTION WITH DRAWING NO. BRT-TG-XX-ZZ-DR-HI-0302, BRT-TG-XX-ZZ-DR-HI-0311 AND BRT-TG-XX-ZZ-SP-HI-0300.
4. CHAINLINK FENCE TO MATCH EXISTING AND TO COMPLY WITH REQUIREMENTS LISTED IN HCD H11

## LEGEND

- SITE BOUNDARY
- PROPOSED GUARDRAIL VERTICAL BAR INFILL
- PROPOSED WOODEN POST AND RAIL (H15)
- PROPOSED CHAIN LINK (H11)
- EXISTING FENCE TO BE RETAINED / REINSTATED
- EXISTING FENCE TO BE REMOVED

Received - 9 September 2024
Planning Applications Group

MATCH LINE

FOR CONTINUATION REFER TO DRG BRT-TG-XX-ZZ-DR-HI-0302

MATCH LINE

C01

PROPOSED TUNNEL PORTAL

## SIGNIFICANT RESIDUAL HAZARDS

| RESIDUAL HAZARD | STAGE | SUGGESTED CONTROL MEASURE |
|---|---|---|
| 03-01 STRIKING UNDERGROUND SERVICES WHEN EXCAVATING FOR FENCE POST INSTALLATION | C, M | SOME OF THE PROPOSED FENCING RUNS ABOVE EXISTING UNDERGROUND UTILITIES, WHICH MAY POSE A HAZARD TO OPERATORS DURING FENCE INSTALLATION, DEPENDING ON THE DEPTH OF THE UTILITIES.<br>HAND DIGGING AND CAT SCANNING TECHNIQUES SHALL BE UNDERTAKEN TO LOCATE SERVICES/UTILITIES AND RUN CLASH DETECTION CHECKS. MARK UP ON SITE IF REQUIRED. NO WORKS TO BE UNDERTAKEN WITHOUT A VALID PERMIT TO DIG.<br>TEMPORARY DIVERSION OF UTILITIES MAY BE REQUIRED TO UNDERTAKE WORKS, A PLAN OF NEW LOCATION SHOULD BE RECORDED FOR USE WHEN TEMPORARY DIVERSIONS ARE NO LONGER NEEDED. |

NOTE: The above hazards do not include every hazard or assumption, but identify significant residual construction hazards that are not likely to be obvious to a competent contractor and those that could be difficult to manage effectively. Refer also to the designer's risk documentation.

SHEET 1
SHEET 2

KEY PLAN

| REV. | BY | CHK'D | APP'D | DATE | DESCRIPTION |
|---|---|---|---|---|---|
| C01 | HH | JR | JR | 20/02/23 | ISSUE FOR CONSTRUCTION |
| P05 | LD | LD | MJH | 12/08/21 | FENCES LAYOUT UPDATED TUNNEL PORTAL ADDED |
| P04 | GKC | LD | MJH | 11/06/21 | LAYOUT & TEXT NOTES UPDATED |
| P03 | AMG | LD | MJH | 21/05/21 | TRAFFIC ISLAND AND EARTHWORKS AMENDED |
| P02 | MS | LD | MJH | 31/03/21 | CHANGES FOLLOWING GABION WALL DESIGN |
| P01 | MS | LD | MJH | 01/02/21 | FIRST ISSUE |

| CODE | DRAWING STATUS |
|---|---|
| A1 | FOR CONSTRUCTION |

**Tony Gee and Partners LLP**
8th Floor, International House
Dover Place,
Ashford, Kent.
TN23 1HU
**Tel: 01233 639787**
www.tonygee.com
Consulting Engineers

Kent County Council kent.gov.uk

Balfour Beatty

# BEAN TUNNEL
# TUNNEL AND HIGHWAY DETAILED DESIGN

## HIGHWAYS FENCING PLAN LAYOUT

SHEET 1 OF 2

DRAWING. No.
BRT-TG-XX-ZZ-DR-HI-0301

| DRAWN : BPH | DESIGNED : MS | REVISION |
|---|---|---|
| SCALE : 1:250 | ORIGINAL SIZE : A1 | C01 |